

# **Why are Opening New BLS-3 and BSL-4 Facilities Often Delayed by Years?**

**Barbara Fox Nellis, SM(NRCM), RBP, CBSP**

**Barb Nellis Consulting**

**Sarasota, Florida**

## Or a Better Title?

- The Challenges of User Expectations & Requirements vs the Architect & Engineer Specifications & Direction vs Management Goals & Budget vs Safety & Regulatory Requirements in Designing, Commissioning & Opening for Use Any High Containment Facility!

# All is not a Patagonia



02/19/2011

# Sometimes it's Antarctica



# A Few Definitions

- ❑ BSC – Biological Safety Cabinet
- ❑ BSO – Biosafety Officer
- ❑ BSL – Biosafety Level from 1 (lowest) to 4 (highest)
- ❑ FH – Fume Hood
- ❑ HVAC – Total Ventilation System
- ❑ A&E – Architect & Engineer
- ❑ T&B – Test & Balance
- ❑ VE – Value Engineering

# Why the Operational Delay?

- ❑ Many BSL-3 & BSL-4 facilities, on average, are delayed 1-2 years (Many longer)
  - ❑ User expectations
  - ❑ Systems designed against budget vs use
  - ❑ Regulatory requirements
  - ❑ User changes due to science & direction
  - ❑ No clear “written” guidance

# Facility Design vs User Needs

- ❑ Challenges of the final product
  - ❑ Commissioning against design or new expectations?
  - ❑ Regulatory agency now involved with more stringent expectations?
  - ❑ Why is there never enough air reserve & capacity?

# The Basics Have Not Changed

- ❑ Single pass air – (filtration Risk Assessment)
- ❑ Sustained directional air flow – from clean to most dirty (cold ⇒ warm → hot)
- ❑ Solid, impervious floors, walls & ceilings
- ❑ Capable of being decontaminated
- ❑ Multiple self closing doors – (Air Lock?)
- ❑ Certification capable (AAALAC)
- ❑ Commissioning against expectations



# Case Study

- ❑ Multi-story, multi-wing biological & chemical research facility
  - ❑ Significant flammable solvent volumes
  - ❑ Recombinant DNA & other biological agents
  - ❑ Radioactive isotopes
  - ❑ Tight budget restraints

# Who Wants What?

- ❑ The users want lots of working space with all the bells & whistles
  - ❑ Be able to use large volumes of chemicals
  - ❑ Be protected from mixing chemicals & biologicals
  - ❑ BSCs, Fume hoods & autoclaves near by
- ❑ The management - low cost
  - ❑ Cuts out a fan bank (VE)
  - ❑ Allows common plenum (VE)
  - ❑ Removes the only freight elevator (VE)
  - ❑ Assumes flammable solvent volumes can be controlled by safety person & users
  - ❑ Eliminated autoclave canopies over all units

# Design Issues due to VE

- ❑ Major air capacity issues
- ❑ Building so positive the doors will not close without an effort
- ❑ No freight elevator & only one people elevator available for all three wings
- ❑ All fume hoods ganged with the main facility exhaust
- ❑ Door grills creating a significant fire issue

# Can This Facility be Commissioned?

- ❑ Not enough exhaust fans
- ❑ Current fans running at maximum
  - ❑ Burning out within 2-4 months on average
- ❑ Hallways becoming the “common plenum”
- ❑ Sustained directional air flow not possible
- ❑ Other issues
  - ❑ Not all deck to deck walls
  - ❑ Too many wall & door openings for air transfer purposes rather than a controlled ducted system

# Case Study

## □ BSL-3 Laboratories

- Multiple entry layers starting with BSL-2
- Cold, warm & hot areas
- Multiple users per area
- Subject to significant regulatory oversight with the expectation for “zero tolerance positive pressure” even when passing through a doorway with a cart

# Who Wants What?

- ❑ The users want lots of working space with all the bells & whistles

- ❑ Be able to move from lab to lab without disrupting air capture

- ❑ Be protected from all agents

- ❑ BSCs, Fume hoods & autoclaves within the facility

- ❑ The management wants low cost

- ❑ Minimum HVAC – not enough air

- ❑ A&E direction without user needs

- ❑ Work flow issues not considered

- ❑ Commissioned without activity

- ❑ Assumed Regulators would be happy

# Design Issues

- ❑ A&E fell short of understanding what “sustained directional airflow” really meant
- ❑ Exhaust ducts placed directly over hot lab doorways on the warm side & over ducted & stand alone Biosafety Cabinets
- ❑ Multiple supplies with few exhausts per laboratory (B2 cabinet expected to exhaust for a small laboratory)

# Can This Facility be Commissioned

- ❑ A balancing & control nightmare
- ❑ Was not designed for the regulatory expectation of zero tolerance air reversal
- ❑ Baffling all the badly placed exhaust & supply vents & closing excess supplies
- ❑ Depending upon ducted BSC & Autoclave canopy for additional exhaust



# Show Stoppers

- ❑ Some common Challenges to Certification & Commissioning
  - ❑ Not enough air
  - ❑ Not enough controls or inadequate controls
  - ❑ No test ports
  - ❑ Poor seals all around
  - ❑ Changing expectations
  - ❑ Regulators will not accept


## More Examples

- ❑ Multiple 100% exhaust ducted biosafety cabinets ganged with the fume hoods & building exhaust
  - ❑ Opening or closing the fume hood disrupts the airflow & alarms the BSC
  - ❑ Opening & closing room doors has the same effect
  - ❑ Control system cannot adjust for the change

# Examples Continued

- ❑ Air lock vs multiple entry layers
  - ❑ Air locks expensive
  - ❑ Can you accomplish the same without?
  - ❑ Maintenance aspects
  - ❑ Overall reliability & control
  - ❑ Risk Assessment must be completed
- ❑ Regulatory required?

# User Requires & Expects the Following Air Flow within this ABSL-3



# What Can You Do?

- ❑ Users & Maintenance Personnel
  - ❑ Get involved
  - ❑ Spell out your specific needs
  - ❑ Document the specifications
  - ❑ Refer to regulations where they impact – get them involved for support of requirements
  - ❑ Settle for a smaller footprint vs allowing HVAC value engineering
  - ❑ Don't settle for a facility that cannot be maintained

# What Can You Do?

## ☐ Safety

- ☐ Do your homework – understand both the user & construction team needs
- ☐ Educate the management team
- ☐ Sell the necessity of involvement from the early design through operational readiness
- ☐ Be the liaison to all parties

# What Can You Do?

## □ Certifiers

- If you are already a vendor – try to input to the design/construction team
- Can't get to the team – then get to the BSO
- You can end up with a certification nightmare if the entity planners do not understand

# What Can You Do?

## ❑ Commissioning Agents

- ❑ If you have been involved at the start – don't fear being heard
- ❑ If you know you will be the agent – get to the BSO or design/construction team
- ❑ Savvy entities will involve the agent from the beginning



# Too Late the Facility is at 75-100%

## □ Suggestions:

- Be honest – if the facility cannot be certified or commissioned in its current configuration – tell them so
- Ask what the Regulatory requirements are (NIH/CDC?)
- Suggest solutions to the problems – even redesign as needed
- Don't just certify or commission for that moment in time! It will not last once the facility is in operation.

# Thoughts from Both Sides

## ❑ Users

- ❑ Feel they explained themselves completely
- ❑ Assumed the construction team knew & understood their terminology
- ❑ Assumed the construction team knew & understood the regulations that applied to the work

## ❑ A&E

- ❑ Feel user expectations were not reasonable
- ❑ Feel users did not explain properly
- ❑ Feel users kept making changes
- ❑ Needed documented detailed specifications agreed to by both sides

# Personal Experience

- ❑ Major issues common to many facilities
  - ❑ Early calculations done without considering all the potential equipment – all active & in use
  - ❑ Early T&B conducted without all large air, water and heat users on line
  - ❑ T&B in general conducted without activity
  - ❑ Commissioning done without activity information
  - ❑ Excess air capacity is the first to go via Value Engineering & cost control
  - ❑ Did not understand Regulatory Requirement

# Is There a Solution?

- ❑ Most important components
  - ❑ Initial meetings with users, A&E, commissioning agent, safety, management & maintenance (those who must keep it up & running)
  - ❑ Complete & very detailed specification list & why
    - ❑ Signed off by all parties
    - ❑ Include specific regulations where applicable
  - ❑ Users & safety represented (with authority) on the construction team throughout the process

# A Final Thought

- ❑ The Ancient Inca Indians had engineering skills, calendars & time dials
- ❑ They even controlled air flow!



Machu Picchu, Peru



# Questions?



Gentoo Penguins, Falkland Islands