


Seriously, an insectary at a primate center?

Kalpana Patel, RBP and Maureen Thompson, RN, BSN, COHNs, RBP

Yerkes National Primate Research Center, Emory University



18

INTRODUCTION

C E N T E R

- Anopheles mosquitos are a critical component to study human malaria. The nonhuman primate (NHP) model replicates the natural progression of the disease in humans.
- Resources for the Anopheles mosquitos were no longer available to researchers.
- This led to the discussion, could we provide this resource at the Yerkes National Primate Research Center. (see Fig. 1)

Recruited subject matter experts, researchers, biosafety professionals, entomologists, and facilities personnel



Determined feasibility of renovating existing NHP facilities to serve as a mosquito insectary using the Arthropod Containment Level-2 guidelines



Identified a NHP testing space (ABSL-2) that could be retrofitted to accommodate the mosquito insectary

Figure 1. Process

METHODS

A preconstruction risk assessment included mosquito control, construction near NHP housing, and security. (see Fig. 2)

entry Air Curtains Dynotraps Mosquito



Construction Concerns

Security

Wall to separate from NHP Increase monitoring of animal stress Additional enrichment provided

Insectary key card access:



 to rearing room Figure 2. Pre-construction risk assessment

to feeding room

Facility was renovated. (see Fig. 3)

at entry




Figure 3. Renovation of NHP testing facility into a mosquito insectary

Research risk varied in each room. (see Fig. 4)

 Incubation and dissection or Malaria infected mosquitos.

Rearing Room

 Uninfected anopheles mosquitos are reared in environmental chamber.

Feeding Room

 Malaria positive NHP are transported to this space for mosquito feedings.

Figure 4. Transition of research risk

The risk assessment process was used again to develop standard operating procedures, determine personal protective equipment, and training requirements. (see Fig. 5)





Training Training for feeding room access only. Additional

training for entering rearing room or dissection room.

Figure 5. Post construction risk assessments

Project challenges. (see Table 1)

Table 1. Problems Encountered

Large equipment

- Size of incubators were too large to fit through
- A larger doorway was added (then sealed) to the feeding room to fit incubators.

Level floors

- Doors were not level therefore, sweepers would get caught when door opened.
- SOPs and training reflected that each door had to be closed before another could be opened.


Screens on inside of vents did not allow for



- easy visual inspection and cleaning.
- Addition screens put on outside of vents.

Feeding larvae

- Corn syrup used for feeding initially caused fruit flies.
- A change to a graduated sugar mixture eliminated the fruit flies.




Controlling

- Sinks were too small to disinfect rearing trays.
- Large sealed plastic container used to disinfect trays, until sinks can be replaced.

Incubators were not connected to a water


- source, water is required to maintain humidity. humidity
 - Temporary fix, lab using carboy for water



- Clogged drain in environment chamber. Facilities addressed drainage problem.

RESULTS

- Risk assessments were a valuable tool used to determine:
 - The feasibility, location and research risk.
 - Engineering controls, standard operating procedures, and training.
 - Best solutions to address construction and implementation challenges throughout the process.



CONCLUSIONS

- A mosquito insectary is possible at a nonhuman primate center with the use of risk assessments throughout the process.
- The mosquito insectary at Yerkes National Primate Research Center was fully operational as of March 2018.

ACKNOWLEDGEMENTS

Thank you to Tracey Fountain and Dr. Chester Joyner for input and support throughout this project. This project was supported by the National Institutes of Health's Office of the Director, Office of Research Infrastructure Programs, P510D011132.